System Data Sheet




Isocrete Hoor screeds

Isocrete Fast-K Screed



System Design



Description

Isocrete Fast-K Screed is semi-dry cementitious screed incorporating proprietary accelerating, water reducing and shrinkage compensation additives to give a high early strength, rapid drying screed.

Standard and Heavy Duty Isocrete Fast-K Screed can be utilised in bonded, unbonded or floating screed constructions.

Uses

Fast track construction and refurbishment projects where the screed needs to be trafficked or overlaid quickly. Typical fast track applications include shopping centres, hospitals, schools, retail outlets.

Benefits

- Early traffic by following trades (8 hrs at 20°C)
- Early installation of sensitive finishes (7 days for 50mm thickness @ 20°C and 50% RH)
- Low shrinkage, minimises cracking
- High abrasion and impact resistance
- Use with underfloor heating systems
- Easy to use excellent workability properties, can be pumped

Project References

Available on request.

Model Specification

Product: Isocrete Fast-K (Standard / Heavy Duty) Preparatory work and application in accordance with suppliers instructions. Manufacturer: Flowcrete Middle East FZCO Telephone : Customer Service +971 4 886 4728

Bonded

_____ mm Standard (or Heavy Duty) Isocrete Fast-K to be supplied and laid bonded with M-Bond Extra epoxy resin combined dpm and bonding agent to a suitable sound shotblasted or scabbled and vacuum cleaned in situ concrete base.

Unbonded

_____ mm Standard (or Heavy Duty) Isocrete Fast-K reinforced throughout with steel fabric to BS4483 ref. D49 (or reinforced throughout with Isocrete PP Fibres with a strip of steel fabric to BS4483 ref. D49 across day joints) to be supplied and laid on a sound and clean bituminous damp proof membrane.

Floating

_____mm Isocrete Fast-K, reinforced throughout with steel fabric to BS4483 ref. D49 (or reinforced throughout with Isocrete PP Fibres with a strip of steel fabric to BS4483 ref. D49 across day joints) laid on and including _____ mm ____ insulation board.

Model specifications are also available for various other screed configurations. Please consult Flowcrete Technical Advisors.

Products Included in this System

Isocrete Fast K-Screed with Isocrete PP Fibres Bitumen Damp Proof Membrane

Detailed application instructions are available upon request.

Installation Service

The installation should be carried out by a Flowcrete approved applicator with a documented quality assurance scheme. Obtain details of our approved contractors by contacting our customer service team or enquiring via our website at www.flowcrete.ae

Smoothing Compounds

Isocrete Fast-K screeds are generally finished suitably to receive floor finishes direct. Damage to the surface of unprotected screeds may mean that a smoothing compound is necessary. However, it should be noted that the applicators of modern thin flooring will often recommend a smoothing compound on even well finished semi-dry screeds.

If smoothing compound required:

Primer:	Isocrete Primer @ 0.05 kg/m ²
Smoothing compound:	Isocrete 1500 (3mm) @ 5.1 kg/m²

Technical Information

The figures that follow are typical properties achieved in laboratory tests at 20°C and at 50% Relative Humidity.

Density (approx.)	1,800 - 2,000 kg/m ³
BRE Test Category BS8204-1	Category A
Compressive Strength (28 days) BS EN 196-1	>25 N/mm ² Standard Fast-K >30 N/mm ² Heavy Duty Fast-K

Speed of Cure (per layer)

	10°C	20°C
Working Time	50 mins	20 mins
Light Foot Traffic	18 hrs	8 hrs
Full Traffic	5 days	3 days
Curing Under Polythene	12 hrs	12 hrs
Drying time to receive		
finishes (BS8203) - from		
removal of curing		
polythene sheet 50mm		
thickness and 50% RH	14 days	7 days

Residual Moisture Content

Before floor finishes are laid, the moisture content of the screed should be checked by the Main Contractor. BS8203 recommends a maximum of 75% RH prior to the installation of sensitive finishes. Moisture in the base will impede the drying of the screed.

A damp proof membrane is required on ground floors and may be required on new concrete slabs to seal in excess construction moisture in the base. For unbonded and floating screeds, a dpm may be specified between the base slab and the screed. For bonded screeds, M-Bond Extra epoxy resin combined dpm and bonding agent may be used.

Note that Isocrete Polymer 70 and grout will introduce water. For the shortest drying times, bond with M-Bond epoxy bonding agent.

Standard and Heavy Duty Isocrete Fast-K Screed

Standard Isocrete Fast-K Screed is suitable for most commercial applications. Heavy Duty Isocrete Fast-K Screed is recommended in heavily trafficked areas of commercial buildings and in similar areas to receive resin floor finishes. (For industrial screeds, consult Flowcrete for appropriate screed specifications).

Important Note

Flowcrete's products are guaranteed against defective materials and manufacture and are sold subject to its standard Terms and Conditions of Sale, copies of which can be obtained on request.

Further Information

To ensure you are specifying a fit for purpose flooring for your project please consult our Technical Advisors on the number below or visit our website to register your interest in specifying one of the most durable floors on the market.